

Seven Months to Dewater a 6000yd³ Excavation


(Observational Method used to
control A 200,000yd³ quicksand 'tank')

for USACE Structure 37A, Pompano Beach, FL

John H. Schmertmann
GeoVirginia 2015

'Flow' of Lecture


- **Site, Objective**
 - **452 Wellpoints, Boils**
 - **Piez & pumping tests**
 - **Dewatering alternatives**
 - **Weighted filter blanket design and construction**
- **Initial dewatering, self-pumping wellpoints**
 - **Final dewatering and slab construction**
 - **Dewatering summary**



Site 100 ft. from Existing Canal Pumping 8000 gpm, Need 5' Deeper



ELEV Range (ft.)



**Thin Layer
Peat over Sand**

**Porous limestone
replaced with sand**

**Uniform fine
sand**


Porous limestone

**Average
geologic
section
based on 6
USACE
SPT
borings
under
40 x 60'
weir slab**

452 Wellpoints in 3 Stages



Flownet matched to wellpoint, piez. and stage gpm data



Date (1)	Head Loss, ΔH		
	Estimated H in rock (2)	Surface of excavation (3)	ΔH , in feet (4)
October 20	-1	-12	11
October 29	-1	-7.5	6.5
November 5	-1	-10	9


Vertical Flow		
Rock elevation estimated (5)	ΔL , in feet (6)	\bar{i}_v , $= \Delta H / \Delta L$ (7)
-30	18	0.61
-30	22.5	0.30
-30	20	0.45

Average vertical gradients to start each of the 3 boils


Pressure relief well pumping tests




Well Pumping Test Section



Pumping one well, drawdown data




Pumping both wells



Summary of Contractors' Dewatering

Approx. Pumping Rate
in thousands of gpm




◎ ELEV OF WATER IN EXCAVATION

- | | |
|--|--|
| a. Stage 1 (longer) completed, 220 wps, tips at -30. | h. 7 new N-borings completed. |
| b. Ditched and backfilled upper limestone. | i. 12" well pumping tests. |
| c. Shortened stage 1, added 36 wps, tips at -24. | j. Decision to attempt gravel blanket scheme. |
| d. Put in temporary stage just inside stage 1, 100 wps, tips at -15. | k. Removed all wps, flooded and started underwater excavation. |
| e. Stage 2 completed, 50 wps, tips at -24.5. | l. Started filter and drain construction. |
| f. Removed temp. 100 wp line. | m. Pumped flooded excavation to below top of gravel blanket (at -10.5) |
| g. Stage 3 completed, 146 wps, tips at -24, CONSULTANT CONTACTED. | n. 1st tests for relief wps. |


Alternate Dewatering Methods

Method	Likely Success	Relative Cost Estimate	Notes
Wellpoints	None	'Infinite'	Failed
Sheet Pile and Tremie Mat	High	100	Conventional
Pressure Relief Wells	Good	125	gpm very high 100,000 +
Grout Top of Limestone	Fair-Poor	90	Continuity?
Gravel Blanket	Unknown	50	New (but intriguing)

Schematic Diagram of Gravel Blanket Method



Setup for piezometer control



Need to import filter gravel 500 mi.
to obtain $\Delta \sigma'_v = +100$ psf

Chattahoochee river gravel:	$\bar{\gamma}' \approx 60$ pcf
Local limestone gravel:	$\bar{\gamma}' \approx 37$ pcf
	<hr/>
	$\Delta \approx 23$ pcf

River gravel increases $\bar{\gamma}'$ by 62%

**500mi
gravel
delivery**



Stockpiling gravel



**Blanket
drainage pipe**





Skin divers installing pipe






**Connecting
drainage
pipe to
sump
platform**




Sump cage




Flownet to gravel blanket

(estimated pumpage 4,200 gpm, actual \approx 1000) ??




Piezometer data after initial dewatering



Computation Sheet No. 10

Expected flow and head conditions for flow to a single wellpoint in a grid of pts.




Estimating pressure relief and flow through low-k layer using self-pumping wellpoints

Aprox. 2000gpm

1000 from sand

1000 from wpts

AVE. ELEVATIONS (ft)




safety weight gravel
coarse gravel blanket
fine gravel filter
low permeability silty sand

natural sand


porous rock

Self-pumping wellpoint field used for pressure relief under gravel blanket


Piezometer check after self pumping wellpoints installed




Water pumped out



below blanket



Removing safety gravel



Starting foundation slab



**Rushing to
finish**

**(time an
enemy)**




**Pouring
concrete**

**Critical
point
passed!**

Dewatering Summary

Approx. Pumping Rate in thousands of gpm



- | | | |
|---|--|--|
| <p>a. Stage 1 (longer) completed, 220 wps, tips at -30.</p> <p>b. Ditched and backfilled upper limestone.</p> <p>c. Shortened stage 1, added 36 wps, tips at -24.</p> <p>d. Put in temporary stage just inside stage 1, 100 wps, tips at -15.</p> <p>e. Stage 2 completed, 50 wps, tips at -24.5.</p> <p>f. Removed temp. 100 wp line.</p> <p>g. Stage 3 completed, 146 wps, tips at -24, CONSULTANT CONTACTED.</p> | <p>h. 7 new N-borings completed.</p> <p>i. 12" well pumping tests.</p> <p>j. Decision to attempt gravel blanket scheme.</p> <p>k. Removed all wps, flooded and started underwater excavation.</p> <p>l. Started filter and drain construction.</p> <p>m. Pumped flooded excavation to below top of gravel blanket (at -10.5)</p> <p>n. 1st tests for relief wps.</p> | <p>o. Initial 50, 2", No. 60 screen, relief wps installed.</p> <p>p. Additional 70 relief wps installed.</p> <p>q. Removed south half of safety gravel.</p> <p>r. Removed north half of safety gravel.</p> <p>s. Foundation slab completed, critical point now past.</p> |
|---|--|--|

HISTORY OF DEWATERING AT STRUCTURE 37A

FT. LAUDERDALE, FLORIDA

John H. Schmertmann

For All the Details, See...

10803

SEPTEMBER 1974

CO3

JOURNAL OF THE CONSTRUCTION DIVISION

DEWATERING CASE HISTORY IN FLORIDA

By John H. Schmertmann,¹ F. ASCE

INTRODUCTION

Dewatering occasionally becomes a surprisingly difficult phase of construction. This paper describes the dewatering of a small foundation in Southeast Florida in 1959-1960 where the difficulty proved an uncomfortable and expensive surprise to both engineers and contractor. Although the contractor bid the dewatering at \$20,000, it actually cost about \$130,000, not including lost-time costs. He expected to do it in 2 weeks but it actually took 7 months! At one point,

Reprinted in ASCE, GSP 180, pp. 95-111

The End

Thank you!